



NOTES:

1. ALL CONSTRUCTION SHALL CONFORM TO THE CITY OF SAVANNAH TECHNICAL SPECIFICATIONS INCLUDING, BUT NOT LIMITED TO, SECTION 02200 - EARTHWORK AND SECTION 03300 - CAST-IN-PLACE CONCRETE.
2. BASE COMPACTION UNDER CURB TO BE 98% (ASTM D698).
3. CONTRACTION JOINTS TO BE SAW CUT NO LATER THAN 24 HOURS AFTER THE POUR.

STANDARD CONSTRUCTION
DETAILS



CURB AND GUTTER DETAILS

PLATE NUMBER:

P02

APPROVED:

SIGNATURE ON FILE
CITY ENGINEER

SCALE: N.T.S.

DATE: FEBRUARY 2009